

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

K-182

FOR FIELD USE ONLY

RECEIVED

DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORMSEE INSTRUCTIONS IN HOW TO COMPLETE NATIONAL REGISTER FORMS
TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS

1 NAME

HISTORIC

Goodings Store; Brick House

AND/OR COMMON

Salter House; CHESTERVILLE BRICK HOUSE (Preferred)

2 LOCATION

STREET & NUMBER West side of Maryland Route 290, 220 feet north of its
intersection with Maryland Route 447.

CITY, TOWN

Chesterville

VICINITY OF

NOT FOR PUBLICATION
CONGRESSIONAL DISTRICT
First

STATE

Maryland

CODE

24

COUNTY

Kent

CODE

029

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE	
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input checked="" type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL	<input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input checked="" type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL	<input type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	<input type="checkbox"/> PUBLIC ACQUISITION	<input type="checkbox"/> ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT	<input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input checked="" type="checkbox"/> YES RESTRICTED	<input type="checkbox"/> GOVERNMENT	<input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL	<input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY	<input checked="" type="checkbox"/> OTHER Empty

4 OWNER OF PROPERTY

NAME

Frank M. Huggins

STREET & NUMBER

Goosehill, Box 127

CITY, TOWN

Chestertown

VICINITY OF

STATE

Maryland 21620

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,

REGISTRY OF DEEDS, ETC.

Kent County Courthouse

STREET & NUMBER

CITY, TOWN

Chestertown

STATE

Maryland 21620

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

☐ FEDERAL ☐ STATE ☐ COUNTY ☐ LOCALDEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

DESCRIPTION

K-182

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input type="checkbox"/> ORIGINAL SITE
<input type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input checked="" type="checkbox"/> MOVED
<input checked="" type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		DATE <u>1973</u>

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Salter House, originally located on the northwest corner of the intersection of Maryland Route 447 (Morgnec Road) and Maryland Route 290, is thought to have been built circa 1773. The 2½-story brick building (32' x 20') changed ownership many times. It was abandoned in 1970 and vandalized prior to being moved in 1973 by the current owner, Frank M. Huggins. At that time, the house was designated for demolition, having been declared a traffic hazard by the Maryland Department of Transportation, along with three other early buildings at the intersection. The Salter House is the only one of these that remains near the intersection; it is located approximately 250 feet from its original site.

In the relocation, the house orientation was changed from fronting on Morgnec Road, facing south to fronting on Maryland Route 290, facing east. (See attached site relocation plan.) The building was stabilized and the masonry work restored after the move. The thirty foot, three-bay, one and one-half story frame wing with chimney and the one-story, L-shaped shed porch which turned with the highway intersection were destroyed prior to relocation. A fire in the house destroyed the original stair and damaged much of the trim. A new cedar shingle roof was put on the house after its relocation.

The building is an imposing structure, approximately thirty feet high to the ridge, laid in Flemish bond on the important north and east sides, which originally fronted the intersection, with glazed headers on the north gable. Chimneys are in each gable. A simple cornice with crown moulding projected approximately twelve inches at the second floor ceiling level. The fenestration of the house is irregular. The east facade is four bays long, with a door in the first and third bays from the north, and windows in the other two bays on the first floor, four windows on the second and two dormers on this side of the roof. There is one door and no windows on the first floor of the west side, three windows on the second floor, and two dormers on the roof. On the south end there is one door on the west side on the first story and two windows on either side of the chimney in the gable. On the north end a door in the east bay and a window in the west on the first floor are the only openings. Sash on the first floor have 8/12 lights; those on the second have 8/12 lights and the dormers have 6/6 light sash. The first floor windows had paneled shutters and the second story windows and dormers had louvered shutters.

The interior of the house is in poor condition, waiting for rehabilitation, with plaster removed from the ceilings and partitions throughout the structure and partially from the masonry walls. There is one interior masonry wall two stories in height. (See floor plan.)

The first floor is divided into two rooms, each with two exterior doors, plus a third door in the south room that provided access to the frame addition. The large (north) room on the first floor is thought to have been a tavern room and later a store. It has beaded joists at the 9' high ceiling, probably originally exposed. The plaster ceiling and crown moulding that were probably added later have been removed. Remains of door and window trim indicate that a simpler style of wood trim was used throughout the remainder of the house. A flue runs up to the chimney stack at the north end, but there are no fireplaces in this end of the building. The small (south) room has a fireplace and does not have beaded ceiling joists. It is thought that the masonry

SEE CONTINUATION SHEET #1.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

K-182
FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CHESTERVILLE BRICK HOUSE

Kent County

CONTINUATION SHEET Maryland

ITEM NUMBER 7

PAGE 1

(DESCRIPTION CONTINUED)

wall dividing these two rooms originally had a smaller passage or door between the two, rather than the wide opening that currently exists.

Access to the upper floors was by a narrow winding stair; the original stair, which was destroyed by fire, has been replaced by a new duplicate. The stair leads from the north (store) room to a small hall on the second floor.

The plan of the second floor consists of the stair hall on the east and a small room on the west in the center, flanked by two bedrooms at either end. The south bedroom is enclosed entirely by brick walls, and has a fireplace on the south wall. A small paneled closet with three shelves is above the firebox, and opens to the east side of the fireplace. The north bedroom is separated from the hall and small room by frame partitions of vertical beaded paneling that were furred on both sides and plastered. This paneling was probably exposed at one time. Ceiling height on the second floor is 8'4".

The stairs continue to the third floor where there is a room at each end, north and south, with dormers on the east and west sides. On the south end there are two small windows flanking the chimney. Ceiling height on the third floor is 6' 10".

Door and window trim remains in the building indicating that the two upper floors had similar window and door trim to that in the first floor room, progressing from more elaborate on the first floor to least elaborate on the third floor with similar moulding details.

SIGNIFICANCE

K-182

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input checked="" type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

The intersection of Maryland Routes 290 and 447 has a long history as a commercial center, beginning in the 18th century. Until 1973 three 18th century structures stood here, on the northeast, southwest and northwest corner. They were the remains of what had grown into a small village during the 19th century. The Maryland Department of Transportation decided to demolish the buildings as they sat right on the intersection and were regarded as a traffic hazard blocking the driver's view. The Chesterville store (in 1860 G.W. Spry's store and in 1877 store and post office), a small brick structure, was moved to the Howard Johnson's tract on U.S. Route 301 in Kent County. The frame hotel (in 1860 Jos. Morris' hotel and in 1877 J. Curey's property) was moved to the Kent County Farm Museum site near Kennedyville. Only the Brick House or Salter House remains at the intersection, and it was moved 250 feet north of its original location.

The Brick House was constructed in the 18th century, probably soon after 1773. Its floor plan reflects its use as a commercial building, with two rooms of very unequal size, the smaller one with a fireplace and the larger one with only a flue, probably for a stove, dating from the 19th century. The presence of two doors in each of the first floor rooms also suggests that this was a building in public use.

The 1½-story frame wing had two rooms on each floor and a central chimney. This was destroyed in the 1973 move. Another 1½-story, frame wing will be added during restoration.

In August, 1773 William Woodall sold three-quarters of an acre to Isaac Spencer for £30. The property was described as "lying at New Market Crossroads" and "containing about ¾ acre...being part of Vianna." It was bounded on the south and east by two main roads, on the west by Lambert Smith's lot and on the north by "Mr. Bootes' land." (DD4/234.) Spencer built the present house soon after purchasing the lot. He sold it in 1814 for \$1,600., and the deed reads in part: "All that lot of ground in New Market...beginning at the corner of the Brick house... including the house kitchen and garden as occupied by Benjamin Riley." (BC8/176.)

By 1840 the post office had been established in New Market and its name changed to Chesterville. (JNG7/235.) Aaron L. Gooding bought the property, ¼ acre, in 1857. (JKH 1/87.) Rebecca V. Gooding acquired the property from Gooding's estate in 1879; she was probably his wife. (DCB 5/272.) Martenet's map of Kent County shows the Brick House as "A.L. Gooding's Store" in 1860. The 1877 atlas of Kent and Queen Anne's Counties shows it as "Mrs. Goodwin Store," probably an error, meaning Mrs. Gooding's. Mrs. Gooding's will mentions "my house, Store, Lot and appurtenances, in Chesterville...." (JCS 1/32.)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

K-182
FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CHESTERVILLE BRICK HOUSE
Kent County

CONTINUATION SHEET Maryland

ITEM NUMBER 8 PAGE 2

(SIGNIFICANCE CONTINUED)

The 1959 deed for the property, from Joseph R. Spry and wife to George R. Salter and wife identifies this building as that "commonly known as the Brick House." It has since picked up the common name of the Salter House.




The present owner plans to restore the exterior of the house, including the porch on the (now) north and east sides and to renovate the interior using the small amount of original fabric that remains there. A frame wing of the same proportions as the old one will be built on the (now) south end of the house.




K-182

1877 Atlas of Kent and Queen Anne's Counties.

GEOGRAPHICAL DATA

UTM REFERENCES

B   
ZONE EASTING NORTHING

D   

Beginning at an iron post on the west side of Maryland Route 290, 221.89' north of the center line of Morgnac Road (Maryland Route 447), running 200' north along Route 290 to an iron post, then west 217.80' to an iron post, then south 200' to an iron post, then east 217.80' to the point of beginning.

STATE	CODE	CDUNTY	CODE
-------	------	--------	------

STATE	CODE	COUNTY	CODE
-------	------	--------	------

NAME / TITLE M. Hamilton Morton, Jr., AIA
Pamela James, National Register Coordinator

ORGANIZATION

Architect/Maryland Historical Trust

DATE

January 1978

STREET & NUMBER

TELEPHONE

15th and New York Avenue, NW, Suite 639/21 State Circle (202) 628-1397/(301) 269-2438

CITY OR TOWN

STATE

Washington/Annapolis

D.C. 20005/Maryland 21401

THE EVALUATED SIGNIFICANCE OF THIS PROPERTY WITHIN THE STATE IS:

NATIONAL _____

STATE _____

LOCAL

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

STATE HISTORIC PRESERVATION OFFICER SIGNATURE

TITLE

STATE HISTORIC PRESERVATION OFFICER

DATE _____

FOR NPS USE ONLY

I HEREBY CERTIFY THAT THIS PROPERTY IS INCLUDED IN THE NATIONAL REGISTER

DATE _____


DIRECTOR, OFFICE OF ARCHEOLOGY AND HISTORIC PRESERVATION

ATTEST:

DATE _____


KEEPER OF THE NATIONAL REGISTER

1501825201

1. STATE Maryland COUNTY Kent TOWN Chesterville VICINITY STREET NO. Rt. 44 ¹ / ₂ , at Rt. 290 ORIGINAL OWNER ORIGINAL USE dwelling or tavern PRESENT OWNER George Salter PRESENT USE dwelling WALL CONSTRUCTION brick NO. OF STORIES 2 ¹ / ₂		HISTORIC AMERICAN BUILDINGS SURVEY INVENTORY K-182	
		2. NAME Salter House DATE OR PERIOD 18th century STYLE colonial ARCHITECT BUILDER	
		3. FOR LIBRARY OF CONGRESS USE	
4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION OPEN TO PUBLIC NO			
<p>The Salter House, located on the northwest corner of the intersection at Chester-ville, is a two and one half story brick building, laid in Flemish bond on the south^A and east sides, with glazed headers on the east gable. The south facade is four bays long with two dormers on the "A" roof. Sash in the first story windows is 2/2, second story is 8/12, and attic is 6/6, with paneled shutters on the first story and louvered shutters on the second A/A/A/A/ story and dormers. Doors are located in the first and third bay from the east gable and one in the east gable. There are no windows on the first story of the north side and only one door, on the west ^{end} side of the facade. The second story has three windows with 8/12 sash and two dormers on the tin roof. A porch covers the first story on the east and south sides and the north door. A three bay 1¹/₂ story frame wing is built off the east gable. The entire structure has been painted red at some ^{time} time, not recently. There is a chimney in each gable and one in the center of the wing.</p> <p>On the map of 1877, this building was called Mrs. Goodwin^{is} Store. Prior to the time when Chesterville has its own post office, the town was called New Market.</p>			
5. PHYSICAL CONDITION OF STRUCTURE Endangered possibly Interior poor Exterior poor			
6. LOCATION MAP (Plan Optional) 		7. PHOTOGRAPH	
8. PUBLISHED SOURCES (Author, Title, Pages) INTERVIEWS, RECORDS, PHOTOS, ETC.		9. NAME, ADDRESS AND TITLE OF RECORDER Michael Bourne DATE OF RECORD Sept. 12, 1968	

SUPPLEMENTAL INFORMATION AND PHOTOGRAPHS MAY BE ADDED ON SHEET OF SAME SIZE

K-182





Chesterville Brick House
(Salter House)
Kent County, Maryland

Floor plans
M. Hamilton Morton, Jr.
Architect

(scale inaccurate as
drawings have been
reduced)

January 1978



places: Hearths:

fireplace on W. wall of W. room now completely sealed + plastered over - hearth covered by later flooring. See sketches in W. room (2nd fl.) w/ ca. 1850 mantle. Smaller fireplace in E. room of 1st floor.

Mantels and Chimney Pieces (including paint evidence):

(2nd fl.) mantle
None 1st floor
mid 19th century on 2nd.
none in attic
Chimney at east end later introduction. Blocks in original window opening at 2. end.

Fireplace equipment:

none

Staircases: Type and Location:

Narrow stairs at south end of center partition - enclosed by located boards. badly worn in recent times. Construction show, ruined + windowed framing.

Treads and Risers:

5 treads. 7 risers.

Newel Posts and Balusters:

19th c. rail w/ turned balusters at 2nd floor.

Soffits:

horizontal beaded boards, 1st. plastered on second

Paint Evidence:

Handrail Profile




Brackets

Hardware

Modern knob type - some evidence of earlier, 4. 1st fl. knob.

In-Furniture and Mechanical Equipment, and Evidence of Room Uses

Moulding Profiles (including mullions)



Locations:

1. baseboards - W. room, 2nd floor + attic
2. S. door architrave, W. room
3. window
4. 2nd floor west fireplace exterior - all windows
5. ext. cornice
- 6.
- 7.
- 8.


K-182

MORGENEC RD.



ASSUMED LOCATION OF
SALTER HOUSE PRIOR
TO RELOCATION

PRESENT LOCATION



227.89'

217.80'
N 62° 00' W



N 28° 00' E 200.00'

528° 00' W 200.00'

MD. RTE 290

SALTER HOUSE RELOCATION
CHESTERVILLE MD.

SCALE 1" = 60'



SAMUEL S. HOPKINS, Proprietor of Urieville Flouring Mill. Best Grades of Family Flour manufactured and kept on hand for sale at all times, also Custom Work done at all times. All persons are solicited to give me a call. 2 1/2 miles from Kennedyville.

J. P. POTE, Blacksmith at Urieville. All kinds of Blacksmithing done with neatness and dispatch. All persons wanting anything in my line will please give me a call. 2 1/2 miles from Kennedyville.

A. STRONG, Wheelwright at Urieville. All kinds of Wheelwrighting done with neatness and dispatch. Persons wanting anything in my line will do well to give me a call. Shop 2 1/2 miles from Kennedyville.

J. L. WILMER, Proprietor of Goose Hill Mill. 4 miles from Chestertown. The best Grades of Family Flour manufactured and kept on hands for sale at all times. Custom Work done at all times.

H. C. PENNINGTON, Proprietor of Kennedyville Hotel. First-class accommodations for all.

SASSAFRAS P. O. BUSINESS REFERENCES.

T. P. DAVIS, Dealer in Drugs, Medicines, Books, Stationery, &c.

LOUIS EBERHARD, Broom-maker. All kinds of Brooms manufactured to order.

CHESTERVILLE BUSINESS REFERENCES.

MARY E. WATTS, Dealer in Dry Goods, Hats, Caps, Boots, Shoes, Candies, Confectioneries of all kinds, Toilet Soaps, Fancy Articles, &c. Corktown.

JOSHUA DAVIS, Blacksmith. Blacksmithing done in all its Branches. Give me a call.

JAMES CAREY, Proprietor of Chesterville Hotel. Good Stabling attached, and good accommodations at all times. All Guests will be made Comfortable.

SASSAFRAS P. O. BUSINESS REFERENCES.


T. P. DAVIS, Dealer in Drugs, Medicines, Books, Stationery, &c.

LOUIS EBERHARD, Broom-maker. All kinds of Brooms manufactured to order.

DISTRICT

DYVILLE


T C9



Galena Quad

Chesterville
brick house
(Sater house)

K-182





K-182

K-184 Chesterville

212034

Hotel K-184
(Brick House K-182) Spencer Store ca. 1784

HA135

MD1

15-chesv

2-1

REPRODUCED FROM THE ORIGINAL
MANUSCRIPT BY THE NATIONAL ARCHIVES

CIII-H



K-182

~~K-183~~

K-182 C'ville brick house

K-184 C'ville hotel

~~K-181 Spenser Store~~

~~K-182 C'ville Hotel~~

K-183 Chesterville store & Post Office, site c.1780

**MARYLAND HISTORICAL TRUST
LIBRARY**

CIV-N



Salter House

K-182

Anthony C. James

8/1973

Neg. on file @ MHT

View from NW

MHT



Salter House

K-182

Anthony O. James

8/73

Neg. on film 11/14/73

Chimney base looking East
Cellar under frame wing



K. 182 2174 JmK

Salten House from W.



K. 182 Salter House

from SE 2/74 JMK



K. 182 Salter House

from SE 2/74 JMK



K. 182 Salter House

from S. 2/74 JmK



K. 182 Salter House

from NE 2/74 JMK



K. 182 Salter House

From N.E. 2/74 Jmk



K.-182 Salter House

from SW 2/74 JMK



K. 182 Salter House

from NW 2/74 JMK



K. 182 Salzen House Barn

From S. 2/74 JmK



K. 182 Salten House Barn

from NE 2/74 JMK

AA898



K. 182 Salter House Barn
from E. 2/74 JmK





Formerly used as a tavern, a store, and a dwelling, this reminder of Chesterville's heritage is shown en route to a safer location adjacent to its original site.

4570

K. 182

August, 1973 - original negative on file at Maryland Historical Trust.



K-182

Chesterville Brick House



~~Salten~~ ^{House} ~~Manor~~ Rebo.

JMK 2174 K.-182

Cheslerwell built House



N. 182



K. 182



Salter House

Chesterville, Maryland

HISTORIC AMERICAN BUILDINGS SURVEY
(Library of Congress Negative)

Jack Butcher....., Photographer

Date....., 19.....



Salter House
Chesapeake, Maryland
K-182

HISTORIC AMERICAN BUILDINGS SURVEY
(Library of Congress Negative)

Jack Boucher....., Photographer

Date....., 19.....



Safer House
Chesterville, Maryland

K152

HISTORIC AMERICAN BUILDINGS SURVEY
(Library of Congress Negative)

Jack Tucker, Photographer

Date....., 19.....



Salter House
Chesterville, Maryland

K-182

HISTORIC AMERICAN BUILDINGS SURVEY
(Library of Congress Negative)

Jack Baucher....., Photographer

Date....., 19.....



Salter House

Chester ville, Maryland

K-182

HISTORIC AMERICAN BUILDINGS SURVEY
(Library of Congress Negative)

.....*Jack Baucher*....., Photographer

Date....., 19.....



Salter House


Chesterville, Maryland

V 152

HISTORIC AMERICAN BUILDINGS SURVEY
(Library of Congress Negative)

Jack Boucher....., Photographer


Date....., 19.....



Salter House
Chesterville, Maryland

K-1572

HISTORIC AMERICAN ENVIRONMENT SURVEY
(Library of Congress Negative)
.....*Jack Boucher*....., Photographer
Date....., 19.....



Silver House
Chesterville, Maryland
12-18-72

PHOTOGRAPHIC EVIDENCE SURVEY
(Library of Congress Negative)
Jack Bowler
Photographer
Date: , 19